COUNTY OF FRESNO ADDENDUM NUMBER: TWO (2) RFQ NUMBER: 968-5419 OPERATION & MAINTENANCE OF LANDFILL GAS COLLECTION SYSTEM - AADS

Issue Date: January 20, 2016

IMPORTANT: SUBMIT QUOTATION IN SEALED PACKAGE WITH QUOTATION NUMBER, CLOSING DATE AND BUYER'S NAME MARKED CLEARLY ON THE OUTSIDE TO:

COUNTY OF FRESNO, PURCHASING 4525 EAST HAMILTON AVENUE, 2nd Floor FRESNO, CA 93702-4599

CLOSING DATE OF QUOTATION WILL BE AT 2:00 P.M., ON FEBRARY 4, 2016.

QUOTATION WILL BE CONSIDERED LATE WHEN THE OFFICIAL PURCHASING TIME CLOCK READS 2:00 P.M.

All quotation information will be available for review after contract award.

Clarification of specifications is to be directed to: **Jennifer Anderson**, **phone (559) 600-7115 or** e-mail CountyPurchasing@co.fresno.ca.us.

NOTE THE FOLLOWING ADDITIONS, DELETIONS AND/OR CHANGES TO THE REQUIREMENTS OF REQUEST FOR QUOTATION NUMBER: 968-5419 AND INCLUDE THEM IN YOUR RESPONSE. PLEASE SIGN IN BLUE INK AND RETURN THIS ADDENDUM WITH YOUR QUOTATION.

On the <u>Revised Scope of Work</u>, replace the eighth (8th) paragraph with the following:

Condensate collected in the LFG headers is drained into eight automatic pneumatic condensate sumps. Four sumps are adjacent to the Fill Area II, one located on the western side, one located on the south eastern side and two located immediately north of the flare. Three sumps are located along the conveyance header adjacent to the Soil Stockpile Area, one on the southeast side, two on the north side. One sump is located at the current terminus of the header east of Phase III Module 2. See Figure 2 as reference for approximate locations of the automatic pneumatic condensate sumps. Two air compressors (one operating and the other as a standby); located in the flare station, furnish compressed air to the pump in each sump. The condensate collected in these **eight** sumps is pumped into a 3,150-gallon double-walled condensate storage tank. Condensate is disposed of by injecting it into Flare No. 1 or Flare No. 2 using high-pressure electric centrifugal pumps installed in parallel, with one operating and the other as a standby.

ACKNOWLEDGMENT OF ADDENDUM NUMBER Two (2) TO RFQ 968-5419

COMPANY NAME:		
	(PRINT)	
SIGNATURE (In Blue Ink):		
NAME & TITLE:		
	(PRINT)	
Purchasing Use: JA:hrs	ORG/Requisition: 9026 / 9261600070	
G:\PUBLIC\RFQ\FY 2015-16\968-5419 OP & MNTCE OF LANDFILL GAS COLL SYS - AADS\968-5419 ADD 2.DOC		(10/2015)